BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Estimate Cost Rs. 1500000.00

Name of Work: Detailed Estimate for the work of Construction of RO plant Ananthpura in ward no 03, Attur

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	A) CIVIL WORK								
1	KSRB 2-1.1 Earth work in surface excavation in hard soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P No. 5/ Item No. 2.2/ PWD SR 2016-17	cum							
	levelling and lowering		1	5.00	5.00	0.30	7.50		
							7.50	**239.76**	**1798.00**
	Basic Rate	222.00							
	Area Weightage 8%	17.76							
	Grand Total	239.76							
2	KSRB 2-2.2 Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m specification, specification No KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2016-17	cum							
	for RO plant ssm		2	5.10	0.90	1.00	9.18		
			2	2.80	0.90	1.00	5.04		
	RWT		2	3.20	0.75	0.60	2.88		
			2	1.70	0.75	0.60	1.53		
							18.63	**305.64**	**5694.00**
	Basic Rate	283.00							
	Area Weightage 8%	22.64							
	Grand Total	305.64							

3	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 134 (SR 2016-17)	cum							
				Vide Item No. 1+2			26.13	87.26	2280.00
	Basic Rate for loading and unloading	68.00							
	Basic Rate for Haulage upto 4.00 k.m =1.28 X 2.50 X 4	12.80							
		80.80							
	Area Weightage 8%	6.46							
	Grand Total	87.26							
4	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2016-17	**Cum**							
	for RO plant ssm		2	5.10	0.90	0.10	0.92		
			2	2.80	0.90	0.10	0.50		
	RWT		2	3.20	0.75	0.10	0.48		
			2	1.70	0.75	0.10	0.26		
			1	2.00	2.00	0.10	0.40		
	inside		1	4.00	3.50	0.10	1.40		
							3.96	**5256.36**	**20799.00**
	Basic Rate	4867.00							
	Area Weightage 8%	389.36							
	Grand Total	5256.36							

5	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification No. KBS 2.9, No. 6/ Item No. 2.10/ PWD SR 2016-17	Cum							
			1	4.00	3.50	0.45	6.30		
			1	2.00	2.00	0.45	1.80		
							8.10	**137.16**	**1111.00**
	Basic Rate	127.00							
	Area Weightage 8%	10.16							
	Grand Total	137.16							
6	KSRB 5.2.3 Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications KBS 5.1.13 Page No 23/ Item No. 5.6/ PWD SR 2016-17	Cum							
			2	4.95	0.75	0.40	2.97		
			2	2.95	0.75	0.40	1.77		
			2	4.80	0.60	0.60	3.46		
			2	3.10	0.60	0.60	2.23		
	rwt		2	3.10	0.60	0.40	1.49		
			2	1.85	0.60	0.40	0.89		
							12.80	**4521.96**	**57899.00**
	Basic Rate	4187.00							
	Area Weightage 8%	334.96							
	Grand Total	4521.96							
7	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications KBS 5-1.13 Page No. 26/ Item No. 5.9/ PWD SR 2016-17	Cum							
			2	4.65	0.45	0.40	1.67		
			2	3.25	0.45	0.40	1.17		
			2	2.90	0.45	0.40	1.04		
	rwt		2	2.00	0.45	0.40	0.72		
							4.61	**5405.40**	**24908.00**
	Basic Rate	5005.00							
	Area Weightage 8%	400.40							
	Grand Total	5405.40							

8	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 112/ Item No. 15.1 PWD SR 2016-17	sqm							
			2	4.65		0.400	3.72		
			2	3.25		0.400	2.60		
			2	2.90		0.400	2.32		
			2	2.00		0.400	1.60		
							10.24	**104.76**	**1073.00**
	Basic Rate	97.00							
	Area Weightage 8%	7.76							
	Grand Total	104.76							
9	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.876cum and fine aggregates @0.459cum with superplastesisre @• 3lts conforming to IS9103-1999Reffirmed ' 2008 machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses,• string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2016-17	Cum							
	for coping		2	4.65	0.45	0.10	0.42		
			2	3.25	0.45	0.10	0.29		
			2	2.90	0.45	0.10	0.26		
			2	2.00	0.45	0.15	0.27		
	rwt		1	2.00	2.00	0.10	0.40		
	inside		1	4.00	3.50	0.100	1.40		
	for chajja		1	4.40	0.60	0.075	0.20		
			2	0.75	0.60	0.075	0.07		
	for lintel		2	4.40	0.20	0.075	0.13		
			2	3.50	0.20	0.075	0.11		
	flagging concrete		2	4.00	0.75	0.100	0.60		
			1	5.00	0.75	0.100	0.38		
	Basic Rate	6011.00					**4.52**	**6491.88**	**29340.00**
	Area Weightage 8%	480.88							

	Grand Total	6491.88							
10	KSRB 4-6.10 : Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16/ Item No. 4.37/ PWD SR 2016-17	**sqm**							
	chajja		1	4.40		0.600	2.64		
			2	0.75		0.600	0.90		
	lintel	2x2	4	4.40		0.200	3.52		
		2x2	4	3.50		0.200	2.80		
							9.86	**291.60**	**2875.00**
	Basic Rate	270.00							
	Area Weightage 8%	21.60							
	Grand Total	291.60							
11	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S. 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 25/ Item No. 5.27/ PWD SR 2016-17	**sqm**							
			2	4.40		3.00	26.40		
			2	3.50		3.00	21.00		
	parapet		1	4.40		0.40	1.76		
			2	3.70		0.40	2.96		
							52.12		
	deduction Ventilator		2	0.75		0.60	0.90		
			1	2.50		3.00	7.50		
							8.40		
							43.72	**1011.96**	**44243.00**
	Basic Rate	937.00							
	Area Weightage 8%	74.96							
	Grand Total	1011.96							

12	KSRB 4.9.2 providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46/ PWD SR 2016-17	Quintal							
	90kg/cum		0.900	**4.27**			3.84		
							3.84	**6053.40**	**23263.00**
	Basic Rate	5605.00							
	Area Weightage 8%	448.40							
	Grand Total	6053.40							
13	KSRB 15.3.1 : Providing 12mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever reuired smooth rendering, : Providing and removing scaffolding, including cost of materials, labour Curing complete as per specifications. Page No. 122/ Item No. 15.11/ PWD SR 2016-17	sqm							
	inside		2	3.50		3.00	21.00		
			2	4.00		3.00	24.00		
	out side		2	4.40		3.60	31.68		
			2	3.90		3.60	28.08		
							104.76		
	deduction Ventilator	2x2	4	0.75		0.60	1.80		
			2	4.40		0.60	5.28		
							7.08		
							97.68	**162.00**	**15824.00**
	Basic Rate	150.00							
	Area Weightage 8%	12.00							
	Grand Total	162.00							
14	FIXTURES for doors and windows Page No XIV SR 2016-17								
	VENTILATORS Sl No 395,385,402,386								
	Hinges 5" heavyduty	Each	1	4			4	**37.00**	**148.00**
	bottom lock nail	Each	2	5			10	**47.00**	**470.00**
	MS Clamps	Each	2	4			8	**38.00**	**304.00**
	Brass screws 25mm	Each	10	5			50	**2.10**	**105.00**

15	Providing and fixing single shutter glass door of 12mm thick plain Toughened glass (Saint Gobain,Modi float).The door is fixed by using any approved make hardware fitting like patch fitting, pivot, Floor machine, locking arrangements and suitable SS door rails with Floral glass etching for 1/3 portion of door area etc complete. The rate includes cost of all materials, labour, hire of tools & machineries, and as per specification. Page No.310/ Item No. 39.5PWD / PWD SR 216-17	sqm							
			1	3.00		1.50	4.50		
							4.50	**12312.00**	**55404.00**
	Basic Rate	11400.00							
	Area Weightage 8%	912.00							
	Grand Total	12312.00							
16	Providing and fixing Special make glazed Vitrified tiles (Granomite finis) of approved make, quality and colour of sized 6000x600x10mm thick fixed on existing flooring wit ha special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc., complete. Page No. 104/ Item No 14.44 / PWD SR 2016-17	sqm							
			1	4.00		3.50	14.00		
	skirting		2	3.50		0.15	1.05		
			2	4.00		0.15	1.20		
			1	4.50		0.60	2.70		
			1	4.50		0.75	3.38		
							22.33	**1154.52**	**25775.00**
	Basic Rate	1069.00							
	Area Weightage 8%	85.52							
	Grand Total	1154.52							

17	KSRB 14.13.1 Providing precast chequered mosaic tiles dark shade using ordinary grey cement for steps and flooring, with precast 20mm thick, using marble chips of approved colour 7 to 10 nominal size laid in floors, steps and landings on a bed of 12mm thick cement mortar 1:6, mix, jointed with neat cement slurry mix with pigment to match the shade of tiles curing, rubbing, polishing , oxalic acid wash, wax polish, including cost of materials, labour, HOM machinery complete as per specifications. Page No.112/ Item No. 14.28 SR 2016-17								
		sqm							
			1	2.50	2.50		6.25		
							6.25	**1049.76**	**6561.00**
	Basic Rate	972.00							
	Area Weightage 8%	77.76							
	Grand Total	1049.76							
18	KSRB 15-17.2 Applying priming coat over new wood surface and / or wood based surface after brushing with wood primer pink paint including preparing the surface after thoroughly cleaning oil, grease, dirt, and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications. Page No. 114/ Item No. 15.56 / PWD SR 2016-17								
		sqm							
	doors		1	3.00		2.50	7.50		
	window		2	0.60		0.60	0.72		
							8.22	**38.88**	**320.00**
	Basic Rate	36.00							
	Area Weightage 8%	2.88							
	Grand Total	38.88							
19	KSRB 15-17.6 Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications. Page No.118 / Item No. 15.60.1 / PWD SR 2016-17								
		qty same as item no					8.22		
							8.22	**90.72**	**746.00**
	Basic Rate	84.00							
	Area Weightage 8%	6.72							
	Grand Total	90.72							

20	KSRB 15.15.1 Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth cost of materials, labour, complete as per specifications with primer Page No 113/ Item No 15.51.2 / PWD SR 2016-17	sqm							
		qty same as item no					8.22		
							8.22	**97.20**	**799.00**
	Basic Rate	90.00							
	Area Weightage 8%	7.20							
	Grand Total	97.20							
21	KSRB 15-16 Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to given an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications with primer,page No 114 item No 15.53.2/PWD SR 2016-17								
		qty same as wall plastering					4.50		
							4.50	**90.72**	**408.00**
	Basic Rate	84.00							
	Area Weightage 8%	6.72							
	Grand Total	90.72							
22	PROVIDING TRAPEZOIDAL PROFILED SHEET Providing and installing of pre painted Galvolume iron Trpezoidal profiled sheet of approved make 1060mm width (1000mm cover width), 28-30 mm crest height with cest distance of 200 mm c/c with 2nbs at the center for stiffening , The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc –Alu Alloy coating AZ 150 gsm as pe ASTM 1397/A755-550 mpa steel grade 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling /self tapping screws of 25mm length,to be fixed over the existing purlins, rafters channel and trusses No 300/ Item No 38.30 PWD SR 2016-17	sqm							
	GI Sheet (0.5mm)		1	5.00	5.00		25.00		

			1	2.50	2.50		6.25		
							31.25	831.60	**25[illegible]8.00**
	Basic Rate	770.00							
	Area Weightage 8%	61.60							
	Grand Total	831.60							
23	Steel Pre fabricates structure with a 14 Guage (3)" each 60 kg including cutting and transportation complete	kgs							
	M.s Rectangular tubes 1 Length=35.00 kgs = 4.4x5 =22 /6 mtr per length = 4 length x 35 kgs		4	35.00			140.00		
	M.s Rectangular tubes (purlines) 1 Length=35.00 kgs = 8x4 =32 /6 mtr per length = 6 length x 35 kgs		6	35.00			210.00		
	Angels truss = 6 Nos x 2.5 Mtrs x 25kg/ mtrs =375						375.00		
	MS Pipe 50mm dia 14 guage = 6 Nos x 50kg (2 pipe =50 kgs = 100kgs						100.00		
							825.00	95.00	78375.00
								A) TOTAL	**426510.00**
	B) Electrification,wiring and lighting etc to RO Plant								
1 P.No-5 I.No-2.3	Point wiring using Copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2X1.5Sq mm Cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block complete for each outlet. GROUP A KPWD ELectrica SR for 2014-15								
	2.3.1) Short point upto 3Mtr from tapping point to out let via switch box KPWD ELectrica SR for 2014-15	Point	2				2.00	144.00	**288.00**
	2.3.2) Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch box KPWD ELectrica SR for 2014-15	Point	2				2.00	215.00	**430.00**
	2.3.3) Long point above 6Mtr upto 10Mtr from tapping point to out let via switch box KPWD ELectrica SR for 2014-15	Point	2				2.00	334.00	**668.00**

2 P.No-02 I.No-1.1	Open Conduit System Supplying heavy gauge PVC conduit pipe ..... dia .....mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.1.1.1) 19/20mm dia 2mm thick KPWD ELectrica SR for 2014-15	mtr	20				20.00	54.00	**1080.00**
3 P.No-6 I.No-2.5	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A. 2.5.2) 1.5 sqmm. KPWD ELectrica SR for 2014-15	Mtr	50				50.00	18.60	**930.00**
	2.5.1) 1 sqmm.	Mtr	50				50.00	13.00	**650.00**
	2.5.3) 2.5 sqmm.	Mtr	50				50.00	29.20	**1460.00**
	2.5.4) 4 sqmm.	Mtr	50				50.00	42.10	**2105.00**
4 P.No-3 I.No-1.6	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, Finishing with necessary cement plastering complete 1.6.3) 10"x7"x3" (254x178x76mm)	Each	2				2.00	87.00	**174.00**
	1.6.4) 8"x6"x3" (203x152x76mm)	Each	1				1.00	73.00	**73.00**
	1.6.1) 12"x12"x3" (300x300x76mm)	Each	1				1.00	116.00	**116.00**
5 P.No-17 I.No-3.9	Supplying 4mm thick plastic sheet with necessary nitches for fixing switches, regulators etc., and fixing on existing wooden or metal box using N.F. screws. KPWD ELectrica SR for 2014-15	Sqcm	1225				1225.00	0.25	**306.25**
6 P.No-18 I.No-3.8	Supplying and fixing/replacing of 6/16/32Amps electrical accessories on existing switch board GROUP A KPWD ELectrica SR for 2014-15								
	3.15.1) 6Amps SP Switch	nos	1				1.00	35.00	**35.00**
	3.15.3) 6Amps 3 way 5 pin Socket	nos	1				1.00	53.00	**53.00**
	3.15.6) 6 Amps lamp holder	nos	3				3.00	48.00	**144.00**
	3.15.13) 16/6 Amps combined plug and socket with control switch	nos	4				4.00	268.00	**1072.00**
7 P.No-16 I.No-3.7	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 GROUP B 3.7.18) 1000-1200Watts Dimmer KPWD ELectrica SR for 2014-15	Each	1				1.00	447.00	**447.00**

8 P.No-54 I.No-6.2	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 6.16.1) 5-32Amps SP KPWD ELectrica SR. for 2014-15	Each	1				1.00	418.00	**418.00**
9 P.No-55 I.No-7.1	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia KPWD ELectrica SR for 2014-15	No	1				1.00	2727.00	**2727.00**
10 P.No-44 I.No-6.7	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers. 6.7.1) 16Amps	Each	1				1.00	120.00	**120.00**
11 16/3	Supply patty type fluorescent tube light fitting of 4'-36/40 watts fluorescent tube fitting, made out of M.S sheet and stove enameled with low loss open construction copper wound ferromagnetic ballast, starter, locking type brass contact holders mounted on double fold type sheet base fully wired for use on230 Volts A.C Supply including 1No 4'-36/40 Watts fluorescent tube c) Group 'C' KPWD ELectrica SR for 2014-15	Each	5				5.00	340.00	**1700.00**
12 P.No-114 I.No-17.7	Fixing all types and all capacities of fluorescent / false ceiling / spot light / CFL / LED fittings indoor on the wall / ceiling / rafters / girders using 23/0.0076" twin twisted PVC insulated wires, required Nos of round blocks and clamps. 17.7.1) On wall / ceiling / Rafter / Girders KPWD ELectrica SR for 2014-15	Each	5				5.00	98.00	**490.00**

13 65/1	...T POLES. (whereas clearance between Messenger wire and ground is inadequate) a) Supplying and fixing 40mm diat 2.90 thick GI pipe 1.8m long complete with atleast 2 GI pipe 1.8m, long complete with atleast 2 Nos of through bolts 12 mm dia with MS back plate 100x100x6mm dia with eye bolt fixed at top deadeninding messenger wire with masonary patch work etc., complete as per approved drawing (for single phase installations) KPWD ELectrica SR for 2014-15	Each	1				1.00	525.00	**525.00**
14 65/5	INSULATED CABLE ON MESSENGER WIRE Using 2 single core wires for a single phase and 4 single core wires for 3 phase. Supplying and stringing PVC insulated and PVC sheathed 650/1100V class aluminium conductor of size supported by 3.15mm (10 SWG) GI messenger wire with two break insulators one at each end of the span with suspenders at intervals of 0.75m. Each suspender shall be of porcelain reel insulator of suitable core through which insulated wire passes(single core or twin core as the case may be) and this reel insulator shall be fixed to the messenger wire using 2mm (No.14SWG) GI wire suitably bent and twisted. Separate reely insulator shall be provided for each wire, the messenger wire shall be ded-ended on the clamp provided to the departmental pole wide item No.4 above (Page No.56 item No.5 a)Single Phase using 2 Wire e) 16 Sqmm KPWD ELectrica SR for 2014-15	R mtr	55				55.00	85.00	**4675.00**
	BESCOM DEPOSIT CHARGE								**10000.00**
								B) TOTAL	**30686.00**

C) 10000LPD R. O Plant Quotation

RAW WATER PUMP :	
Quantity	1 No.
Type	Centrifugal mono block
MOC & Make	UKL
Motor Rating	0.75 HP
PRESSURE SAND FILTER :	
Quantity	1 No.
Capacity	1000 LPH
MOC & Make of housing	UKL
MOC & Make of cartridge	UKL
Capacity	1000 LPH
MOC & Make of vessel	UKL
Diameter	400 mm
Type of Valve	Single - multiport
Media	Support bed + sand

MICRON CARTRIDGE FILTER :	
Quantity	1 set
Filter Rating	5 microns
Size	20" long
ANTISCALANT DOSING PUMPS :	
Quantity	1 No.
Type	Electro - magnetic
Capacity	1.5 LPH @ 4 Bar
Dosing Tank	HDPE - 50 ltr
HIGH PRESSURE PUMP :	
Quantity	1 No.,
Capacity	1700 LPH
Type of Pump	Vertical Multistage Centrifugal Pump
MOC	SS 304
Motor Rating	2 HP, 3 Phase
Maximum Pressure	12 kg / cm2
Make	UKL
RESERVE OSMOSIS SYSTEM :	
Quantity	1 No.
Capacity	1000 LPH
Module Type	
Membrane Specifications {Polyamide}	
Make of Membrane	UKL
No. of Membranes	
UV STERILISER	
Max. Treatment Flow	1 m3/hr
No. of Lamps	1 No.
Wattage	39W
Efficiency	99.99%
Material of construction	SS 304
PRODUCT WATER QUALITY :	
Appearance	Crystal Clear
Abide by the ISO standards	Yes
S S Tank : 304 grade with 16 gauge 2000 Liters capacity	
304 grade 10 gauge SS Pipe{with steam valve} 25 ft	
COIN BOOTH DISPENSING UNIT	
for 5 liters & 20ltrs separately	
Raw Water Storage Tank	Function – For storage of raw water

	Type/ MOC	Two/Three Layered PE tanks white / transparent in color made from virgin material of Food Grade Quality, suitable for the purpose of providing							
		Storage drinking / potable water. 5000liters capacity.							
	BBMP Approved Rate		1	946000.00			C) TOTAL		946000.00
15	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no142, PWD SR 2016-17)	Cum							
			1	16.00	1.00	0.70	11.20		
							11.20	**86.92**	**974.00**
	Basic Rate	82.00							
		82.00							
	Area Weightage @ 6%	4.92							
	Total	**86.92**							
16	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/ Moorum.KSRRB M100-1:Placing tipper at loading point.loading with front end loader.dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications (Item no17.1,Page no130,PWD SR 2016-17)	Cum							
			Vide Item No. 1				11.20	99.22	1111.00
	Basic Rate	68.00							
	Haulage for 8KM lead SRp-140(2.5*1.28*8)	25.60							
	Total	93.60							
	Area Weightage @ 6%	5.62							

	Total	99.22							
17	KSRRB M2100 PCC 1 KSRRB M2100-10. Plain cement concrete M10 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications MORTH Specification No. 2100 (P No. 218/27.18)	Cum							
	1St B Main CC drain		1	16.00	0.90	0.15	2.16		
							2.16	**5972.04**	**12900.00**
	Basic Rate	5634.00							
		5634.00							
	Area Weightage @ 6%	338.04							
	Total	**5972.04**							
18	Providing laying palin / reinforced cement concrete for Side Drain using M20 normal mix concrete with OPC cement at 300kgs with 20 mm and down size granite metal coarse aggregates @0.69cum and fine aggregates @machine mixed, Well compacted for wall and bottom including centering shuttering Cost of material HOM of machinery curing etc excluding cost of steel as per MORTH Specification No. 1500,1700,2200 walls & bottomof thicknes 15(Page. 265 / Item.No. 37.59.2)	Cum							
	1St B Main Bottom Concrete :-Drain		1	16.00	0.90	0.12	1.73		
	Side walls		2	16.00	0.15	0.60	2.88		
							4.61	7354.28	33889.00
	Basic Rate	6938.00							
		6938.00							

	Area Weightage @ 6%	416.28							
	Total	**7354.28**							
19	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe550(pwd sr2016-17,p.no17,s.no4.46)	Tonne,s							
	0.050 tonne,s / cum						0.23	########	13848.00
	Basic Rate	56701.00							
		56701.00							
	Area Weightage @ 6%	3402.06							
	Total	**60103.06**							
20	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm							
	Covering slabs:-		1	16.00	0.90		14.40		
							14.40	2100.00	30240.00
								D	92962 00
							TOTAL A+B+C+D		1496158.00
21	Miscellaneous charges								
									3842 00
								Total	1500000.00

(Rupees Thirteen lakhs Only)

CERTIFICATE

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per C.S.R. of 2016-17
3 The provisions were made in this estimate are necessary and adequate.
4 This works come under B.B.M.P. limits.

Assistant Engineer

Assistant Executive Engineer
Yelahanka satellitetown Sub Division
Bangalore-64

Executive Engineer
Yelahanka Division
Bangalore-64

Administrative Approval
Accorded For RSIRS laccheny
Head of A/C P 1221
CER NO :.....215..... Dt:..05.02.18

Technical Sanction
Accorded For ISmaller
Head of A/C P.1221
CER NO 5721 1218 Dt:6.02.18

TA CE (YNK)

TA CE (YNK)